



EUROPEAN UNION RULE OF LAW MISSION IN KOSOVO

EULEX KOSOVO

Ndertesa Farmed
“Muharrem Fejza” p.n.
Lagja e Spitalit
10000 Pristina, Kosovo
Tel: +386 (0)43 78 2000
www.eulex-kosovo.eu

CLARIFICATIONS No. 1

**PUBLICATION REFERENCE: EuropeAid/129294/D/SUP/XK
Framework Contract for the Fire Alarm System**

1. Questions regarding the Instructions to Tenderers

Question No	Question	Answer
1.	<p>Can you please send detailed plan layout as there is no site visit applicable?</p> <p>We need to determine distances between camps as many locations are pointed out and from technical specifications we understand this fire system needs to be placed in existing building and there is mention of building work where if need be to place wiring through walls if this will be the case than restore of the walls and painting etc. will be done which shall be unforeseeable events, for this we request detailed plan layout of the camp and areas to be installed of the system to be provide a suitable bid.</p>	<p>A clarification meeting and site visit is applicable. Please refer to Corrigendum No. 1 and Consolidated Tender Dossier.</p>
2.	<p>Since the request is for 30 locations, we would like to arrange site visit for at least 4-5 locations.</p>	<p>Same as answer no. 1 above.</p>

2. Questions regarding the Technical Specification

Question No	Lot No	Question	Answer
1.	Lot 1	Can you please explain if you require addressable fire alarm system, or a conventional fire alarm system	System should be Addressable Fire Alarm System. Please refer to the Corrigendum no. 1 and the Consolidated Tender Dossier.
2.	Lot 1/ Item 1	Specification of fire alarm panel is directly prepared on technical specification of Morley fire panel (definition of button design, cable hole diameter, etc.) We believe this is not in accordance with european legislation (specification written for specific equipment) or can we offer fire panel which doesn't conform perfectly to this criteria (has different keys and different diameter of cable holes, etc.)? Specification of hole diameter and key design has no impact on functionality or functioning of fire panel.	Please refer to the Corrigendum no. 1 and the Consolidated Tender Dossier.
3.	Lot 1/ Item 1	In specification it is stated, we quote »The FACP shall support up to 400 smoke detectors, 50 heat detectors, 30 manual call points, 40 alarm sounders.« (p. 52). Our question is, why to put such a big fire panel if an average systems will be smaller and will not support so many elements (predisposition based on number of detectors and other elements divided by number of locations). Specified panel is for connection of four loops, while we believe that with more specific by location specification you could save some money putting only 2 or 1 loop systems.	Please refer to the Corrigendum no. 1 and the Consolidated Tender Dossier.
4.	LOT 1/ item 1	Does all FACP should be the same specification for all locations, considering that all locations are not the same size.	Technical Specifications of each FACP should be as described on consolidated tender dossier. The quantity of detection devices for each location and specific distribution will be specified on site by the installer, depending on site needs. The amount of the system components (smoke detectors, MCP etc.) installed on each

			location will determine the FACP size and capacity. Please refer to consolidated tender dossier.
5.	LOT 2	In lot 2 specified equipment is Aerosol fire extinguishing. Due to our experience and suggestions of modern standards and guidelines aerosol extinguishing is not suitable for such applications as stated in tender. More modern approach (better for equipment and people) would be extinguishing with NOVEC 1230 or FM200 or Argonite, etc... The question is: Can we offer extinguishing with gases (like NOVEC1230, FM200, etc..) for LOT 2?	As titled: LOT 2: Aerosol Fire Protection System. Only Aerosol Fire Protection System is acceptable.
6.	Lot 2	If these rooms where aerosol is needed are in the same location where FACP of LOT 1, can we plan integrating the LOT 2 into LOT 1.	Items of LOT 1 and LOT 2 will be installed in different locations. Therefore, these two systems can not be integrated.